



Part of the Energy Queensland Group



Operational Update

Energy Queensland Contestable Works As Constructed Requirements

Issue # C-0056 – 05/02/2024

Target Audience:

Energex Accredited Service Providers – Construction

Introduction:

This operational update has been released to reinforce the current requirements for Accredited Service Providers completing As Constructed Workspans.

General

Energex has an As Constructed Drawing Standard that provides the minimum standards for marking up Construction Workspans. This standard is available via the Energex website:

www.energex.com.au/_data/assets/pdf_file/0003/1095960/Network-Data-Standard-As-Constructed-Drawing-Standard-2597742.pdf

Key Sections of the Standard

Section 5.1.2 Construction	Construction staff will mark up any changes to the original design from construction and/or recording supplementary information such as dimensions. The actual network installed must be recorded on the worksplan.
Section 5.1.2 Construction	The mark-ups to the worksplan must be completed in legible handwriting in red pen.
Section 5.1.2 Construction	Construction staff are encouraged to provide feedback to the designer when alterations to the worksplan are required as a result of an incorrect design, or a change based on improving the network.
Section 5.2 The timely return of As Constructed Records	As Constructed records (including required forms/worksplan) are to be received within 10 business days of commissioning of any asset, the electrical completion of a project or the practical completion of a project stage.
Section 5.6 Signing Off	The following fields must be provided when completing an As Constructed Stamp on a worksplan: ☐ Your Name & Signature ☐ Company Name ☐ Phone Number ☐ Date Completed

For more information E-mail contestable@energyq.com.au